
**Chinese Listed Company Stock Code: SZ 300986** 



# GT18 Self Climbing Platform

(Intelligent Building Construction Protective Platform)



#### **GETO Group**

#### **Headquarters:**

Greater Bay Area—No. 13 Heging Road, Tsuihang New District, Zhongshan City, Guangdong Province

#### Southern China Production Base I:

Cuishan Lake Science and Technology Park, Kaiping, Jiangmen City, Guangdong Province

#### Southern China Production Base II:

Huizhou Industrial Transfer Industrial Park, Huizhou City, Guangdong Province

#### **Eastern China Production Base I:**

Guangchang Industrial Park, Fuzhou City, Jiangxi Province

#### Eastern China Production Base II:

Baizhong Industrial Park, Minging, Fuzhou City, Fujian Province

#### **Central China Production Base:**

Hi-tech Industry Development Zone, Xianning City, Hubei Province

#### **Northern China Production Base:**

China Aluminium Industrial Park, Lingu, Weifang City, Shandong Province

#### **Southwest China Production Base:**

Modern Manufacturing Industrial Park, Tongnan High-Tech District, Chongqing City

#### **Northwest China Production Base:**

The Circular Economy Park, Anding District, Dingxi City, Gansu Province

#### **Hainan Production Base:**

Gold Medal Port Industrial Park, Lingao County, Hainan Province

#### **ASEAN Production Base:**

Negeri Sembilan, Malaysia

#### **GETO INDIA**

Regd.Off: C/703, RAAS, VU, Thakur Village, Kandivali East, Mumbai 400101

Operational Office: 8/11 Row House, Suncity Bungalows Shelter Heights, Suncity Rd, Vasai West,

Maharashtra 401202

Mobile: +91 7738091831, +91 9699173295 Email: skp@oxygreen.in; samit@geto.com.cn

Sales Hotline: 0086-760-88589004 E-mail: geto\_market@geto.com.cn



www.getoformwork.com




# **Company Profile**

GETO is a comprehensive service-oriented joint-stock enterprise focusing on aluminur platform, infrastructure construction and precast concreate components. The company tionary base Guangchang of Jiangxi Province. The global management headquarter was se of Zhongshan in Guangdong, the back-land of the Greater Bay Area. Our products sell well and regions around the world. Southern China production base is located in Jiangmen, Gua China production base is located in Guangchang, Jiangxi province; central China prod Xianning, Hubei province; northern China production base is located in Weifang, Shando Trade Port prefabricated construction base is located in Lingao Jinpai Port; ASEAN proc Negeri Sembilan, Malaysia. GETO is the first batch of super-qualified enterprises in the specialization, and intelligence, focusing on research and development, design, product technical services of aluminium formwork and assembly system. We are dedicated high-quality products beyond expectation.

Our company's products cover typical floor aluminium formwork, basement alumir floor aluminium formwork, roof layer aluminium formwork, anti-hollowing formwork, inteself-climbing platform, climbing formwork, tower-type scaffolding, ring lock scaffolding cantilever and other full range of formwork and scaffolding products, as well as precast c the "N+1" one-stop service strategy mode has been realized.

In the future, we will further depend on the improved information basis and apply the cial intelligence and IoT technologies to create the whole-industry-chain ecological ci promote the transformation of the traditional construction to a green and intelligent const






					PAGE
Table			4	Illustration Of Frame System	14
CO	ntent	PAGE		4.1 Setting installa - tion platform	15
	Enterprise Size	03		4.2 Install First Walkway Plate	15
T	-			4.3 Installation of Poling	17
	0.1 GETO Production Bases	03		4.4 Installation of Second	18
	0.2 Cooperation Area	03		Walkway Plate  4.5 Installation of Protective	10
	0.3 Overseas Markets	04		Net	19
				4.6 Set up Inside Closed Turning Plate	20
1	Summary For GT-18 Self Climbing Platform	06		4.7 The end of the Frame Fragment Protection	21
	1.1 Lifting System	07		4.8 Installation of Skirt - ing Board	21
	1.2 Frame System	09			
	1.3 Lightning Protection System	09	<b>5</b>	Installation of Attached Support	22
	1.4 Attached support System	10		System	
	1.5 Control System	11		5.1 Installation of Attached Support	23
2	Application Scope and Condition	11	6	Installation of Lifting System	25
	2.1 Application Scope	11			
	2.2 Application Condition	11		6.1 Installation of Slide-Way	25
				6.2 Installation of Upper and Lower Hanger Frame	26
3	Installation Process	12		6.3 Installation of Lifting Hanging Bracket	27
	Site Installation Process of Climbing Scaffolding	13		6.4 LoadSensorand Electric Chain Hoist Installa tion	28



		PAGE		P.	\GE
_	Installation and Use of Control System	29		Precautions for Use	44
7	7.1 Installation of Electrical Control System	30	10	10.2/A.1.4 GT-18 Self Climbing Platform Lifting Checklist	46
	7.2 Control Operation of Electrical System	30		10.2/A.1.5 Self-checking list for GT-18 Self Climbing Platform adhesive lifting scaffolding after the falling	48
8	Lightning Protection System Installation	32		10.9/GT-18 Self Climbing Platform month checklist	50
	8.1 The lightning protection system consists of a lightning receptor, lightning protection net and grounding wire	33		10.9/Monthly mainte- nance schedule	50
	8.2 Attention when setting lightning protection devic-	33		High Altitude Removal	51
	es		11	11.1 Preparation before dismantling	52
9	Correct Operation of the GT-18 Self Climbing Platform			11.2 Dismantling process	52
		34		11.3 Precautions	53
	9.1 GT-18 Self Climbing Platform lifting process	35	12	GT-18 Self Climbing Platform Installation and Common Use Tools	54
	9.2 After the installation of the frame is completed, notify Party A to check and accept	36		List of Tools for Installa- tion of GT-18 scaffolding	55
	9.3 scaffolding lifting (or		40	Advantages	58
	lowering) must be approved by Party A	39	<b>13</b>	13.1 Advantages	59
				13.2 Production Comparison	59
	9.4 Pre-tightening elec- tric chain hoist steps and methods	43		13.3 Personal Protective Equipment	61
	9.5 GT-18 Self Climbing Platform requirements for use	43	14	Project References	62



#### GETO Production Base:

#### **South China Production Base:**

Jiangmen, Guangdong, China

#### East China Production Base 1#: Guangchang, Jiangxi, China East China Production Base 2#:

Guangchang, Jiangxi, China

#### **Central China Production Base:**

Xianning, Hubei, China

#### **North China Production Base:**

China aluminium formwork industrial park, Weifang, Shandong, China

#### **Hainan Free Trade Port Prefabricated Construction Base:**

Lingao, Hainan, China

#### **Malaysia Production Base:**


Lot 143, 145, Jalan Permata 1/5, Arab Malaysian Industrial Park, 71800 Nilai, Negeri Sembilan

#### Cooperation Area

With a spirit of craftsmanship and perfection, under the call of national "Belt and Road", and adhering to the service tenet of "creating value for customers", we have established long-term partnership with China Top 10 construction companies, such as CSCEC, CREC, MCC, ZHONGTIAN Group, and Country Garden, Vanke, Greenland, Poly, Evergrande Group, etc



#### **Overseas Markets**



#### Headquarter

Tsui Hang New District, Zhongshan, Guangdong-Hong kong-Macao greater bay area, China

#### **Singapore GETO**

Blk 808 French Road #05-157 Kitchener Complex, Singapore

#### **India GETO**

20 Neha Industrial Estate ,Dattapada Road, Borivali East , Mumbai, Maharshtra, India Pin Code 400066

#### **Malaysia GETO**

No 1-2 (Second Floor), Jalan Anggerik Vanilla BF 31/BF, Kota Kemuning, 40460 Shah Alam, Selangor Darul Ehsan, Malaysia

GT18 Self Climbing Platform





# **Summary For GT-18 Self Climbing Platform**

GT-18 Self Climbing Platform is a new scaffolding system developed in recent years, which is predominantly suitable for high-rise buildings and super high-rise buildings. It can rise along with buildings. This system is a technological innovation in the field of scaffolding. For instance, it is not necessary to overhang i-steel for numerous times. Next, it exempts the disassembly and assembly process of the scaffolding.

(After one round of assembly, it can be used until the construction ended). Likewise, it is not limited by the height of the building. Hence, this greatly saved the usage of human resources and materials. GT-18 has more safeguards and plays a greater advantage in high-rise buildings by comparing it with the traditional method of scaffolding.



#### **Components of Self Climbing Platform**











**Lifting System** 

**Frame System** 

**Lightning Protection System** 

Attached Support System

**Control System** 




#### 1.1 Lifting System

Self Climbing Platform


(commonly known as: climbing frame) is the extension and development of the external scaffolding. It is a complete set of construction equipment developed from the traditional concept of building turnover materials. It possesses all the functions of traditional scaffolding, specifically suitable for high-rise buildings and super high-rise buildings. The lifting system consists of slideway, lifting hanging bracket, lower hanger frame, electric chain hoist, and over hanger frame.

GT-18 Self Climbing Platform is one unique kind of scaffolding. It consists of frame system, attached support system, lifting system, control system and lightning protection system. GT-18 Self Climbing Platform is suitable for high-rise and super-high-rise buildings with frame or shear wall structures. Through the application in different sites, it has been proved that its performance is excellent, safe, reliable, stable operation, economic and practical, which brings great convenience to the construction and production formost users.






The lifting system consists of slideway, lifting hanging bracket, lower hanger frame, electric chain hoist, and over hanger frame.



#### 1.2 Frame System


Frame system is the main component of attaching lifting scaffolding, and also the safe operation platform for constructors. The frame structure is mainly composed of walkway plate, poling, protective net, truss, turning plate etc.



#### 1.3 Lightning Protection System

The system consists of air termination, grounding grid and grounding wire.


Note: The high-rise construction lifting platform type high-rise metal frame, which is close to the reinforced concrete structure, is extremely vulnerable to lightning strikes, so lightning protection measures are very important. Every time the frame body is lifted, the grounding cable connecting the frame of the high-rise construction lifting platform and the main body of the building must be removed, and then lifted. After the lifting is completed, connect the frame and the building with a grounding cable of not less than  $\phi 16 \text{mm}^2$ .






#### 1.4 Attached Support System

The attached support system is a supporting structure that is directly attached to the building structure and connected to the vertical main frame to withstand and transmit loads. With support, anti - fall, anti - capsize function.



#### 1.5 Control System

To form the control system, some essential components are computer, mobile phone, tablet PC, remote controller, sensor main control box, sub-control box, cable line and loading sensor.



# **Application Scope and Condition**

#### 2.1 Application Scope

Suitable for industrial and civil (frame, shear wall structure) high-rise buildings

Application Scope and Condition

#### 2.2 Application Condition

Each project is necessary to design the subject construction method statement.


Each project must meet the requirements of "Technical Standard for Safety of Construction Tool Scaffolding".

GT-18 Self Climbing Platform is prohibited from lifting operations in gale above grade 5 (including grade 5), heavy rain, heavy snow, foggy days and nights.



### **Installation Process**

#### **Site Installation Process Of Climbing Scaffolding**





# **Setting Installation Platform**

#### 4.1 Setting Installation Platform

Party A assemble a platform by steel pipe and clamp on the installed flat( Party A assembled according to our requirements and need to pass our acceptance).

Assemble standard:(1) installation platform shall start form the typical floor,platform width need to be control within 1.2M-1.5M.

The distance between the installation platform and the pole is not more than 1.5m, the step of the large crossbar is not more than 1.4m, and the inner row is 0.2m to 0.3m from the outer edge of the building structure.


Reinforcement measures shall be taken when the platform is set up. A set of horizontal tie rods every three meters shall be set at the top of the platform or the position of the lower step frame to unload and reinforced. (Fig.4.1.1)

#### 4.2 Install First Walkway Plate

4.2.1 Assemble on the ground leveling site or erect directly on the platform. Place the bottom walkway board on the bottom of the platform and bolt it together as shown in the figure (Fig. 4.2.1).



(Fig. 4.1.1)



(Fig. 4.2.1)



#### 4.2.2 Set up bottom joint of frame:

Installation standard: wearing safe belt. The connected walkway board is placed in parallel with the structure, the distance between the edge of the walkway board and the wall is installed according to the distance requirement of the shop drawing, and the walkway board is fixed on the installation platform by clamp and cross bars. After installing the pole, no less than 2 wall-attaching joint per 20m.(Fig. 4.2.2)



S/N	Description	Model No.	Qty	Remark
1	Walkway plate	Standard specification	Configure as request	
2	Connecting plate	Standard specification	Configure as request	
3	Electric wrench	XL-80032	1	One person standard
4	Sleeve	22mm、24mm	Each 1	Use with electric wrench
5	Manual wrench	24mm	1	One open-ended and plum combined wrench (one person standard)
6	Matching hexago-nal bolts	M16×50	Configure as request	1 bolt +1 nut+1 spring washer+2 flat washer=1 set

#### 4.3 Installation of Poling

#### 4.3.1 Installation of interior poling

According to the shop drawing marked size install the poling fixing on the walkway plate (Fig.4.3.1), using M16 x 100 hex bolt with flat washer, spring washer, nut connecting the poling fixing part on the first and second hole of poling bottom.

#### **Bolt installation standard:**


wearing safe belt. 1 spring washer, 2 flat washer, 1 M16 x 100 bolt and 1 nut consist 1 set. Ensure that at least 3 teeth are exposed during installation.



(Fig. 4.3.1)

#### 4.3.2 Installation of exterior poling

According to the construction drawing marked size install the exterior poling, The first hole of the poling bottom use M16 X 70 bolt with flat washer and nut connecting with walkway plate, interior and exterior poling connecting by angle truss, it is for temporary reinforcement, In this step, the internal and external bolts of the truss are not tightened, and maintained a little force. After the installation of the second floor walkway plate, the truss is removed and the triangle truss is re-installed according to the construction shop drawings.



(Fig. 4.3.2)

#### Installation standard:

wearing safe belt. 1 spring washer, 2 flat washer, 1 M16 x 70 bolt and 1 nut consist 1 set. Ensure that at least 3 teeth are exposed during installation. Without the first attachment support, at least one fixed connecting rod should be reserved in four positions during erection to maintain the stability of the frame.



(Fig. 4.3.3)





#### **Materials and Tools**

S/N	Description	Model	Qty	Remark
1	Poling	3m/4.5m	Configure as request	
2	Electric wrench	XL-80032	1	One person standard
3	Sleeve	24mm	1	Use with electric wrench
4	Manual Wrench	24mm	1	One open-ended and plum combined wrench(one person standard)
5	Matching Hex bolt	M16×80	Configure as request	1 bolt +1 nut+1 spring washer +2 flat washer=1 set
6	Fixed connecting rod	Ф48	Configure as request	

#### 4.4 Installation of Second Walkway Plate

Installation of interior poling

According to the shop drawing marked size install the poling fixing on the walkway board (Fig.4.3.1), using M16 x 100 hex bolt with flat washer, spring washer, nut connecting the poling fixing part on the first and second hole of poling bottom.

Installation standard: Wearing safe belt, M16 \*100 bolts are used for the erection of the poling fixed and the poling. M16 \*40 bolts are used for the connection between the walkway board and the poling fixed. M16 \*70 bolts are used for the connection between the walkway board and the external poling. M16 \*40 bolts are used for the connection between the walkway board and the walkway board. Walkway boards are installed on both sides of the connecting plate, and M16 \*40 bolts are used for the connection between the walkway board and the connecting plate. 1 spring washer, 2 flat washer, 1 M16 bolt and 1 nut consist 1 set. Ensure that at least 3 teeth are exposed during installation. (Fig.4.4.1)




(Fig. 4.4.1)

#### 4.5 Installation of Protective Net

According to the construction shop drawing, use the M16 $\times$ 70 bolt to reinforce the frame connection bracket on the corresponding position on the pole. Do not lock it first, then fix the protection net on the frame connection bracket through the 7-shaped bolt, and then lock it.

#### Installation standard:

Wearing safe belt,1 spring washer, 2 flat washer, 1 M16 bolt and 1 nut consist 1 set. Ensure that at least 3 teeth are exposed during installation. The frame connector is straight and the 7-shaped bolt is spread out on both sides. (Fig.4.5.1)



S/N	Description	Model	Qty	Remark
1	Electric wrench	XL-80032	1	One person standard
2	Sleeve	24mm	1	Use with electric wrench
3	Manual Wrench	24mm	1	One open-ended and plum combined wrench(one person standard)
4	Matching Bolt	M16×80	1	1 bolt +1 nut+1 spring washer +2 flat washer=1 set
5	Protection Net	Standard specification	1	QTY for single protection net
6	Frame connection bracket	Standard specification	4	QTY for single frame connection bracket
7	7-shaped Bolt	Ф10×120	4	QTY for single frame connection bracket



#### 4.6 Set up Inside Closed Turning Plate

In the bottom of GT-18 Self Climbing Platform and the third floor of the uniform structure (also according to the requirements of the scheme), a turning plate and an extension plate are installed between the inside of the walkway plate and wall. The extension plate and the walkway board are connected by M16 \*40 bolts, and the turning plate is connected by standard parts and plate hinge.(Figure 4.6.1) Installation standard:

- 1. Wearing safe belt.
- 2. When installing the inner extension plate and turning plate, it can be cut on the site according to the actual situation when necessary.
- 3. The extension plate and turning plate should be set continuously along the external structural plane of the building.
- 4. Ensure that the frame and the structure close sealing after the installation of the extension plate and the turning plate is completed, and prevent accidents such as falling persons and objects.
- 5. The extension plate is fixed on the walkway board with M16 \*40 bolt in the field. The turning plate is installed within 10 mm from the outer edge of the extension plate. Hexagonal flange self-tapping nail (ST4.8 x 19) is used to fix the hinge on the extension plate.



(Fig. 4.6.1)

S/N	Description	Model	Qty	Remark
1	Extension plate		Configure as request	
2	Turning plate	1.5M	Configure as request	
3	Hexagonal flange self-tapping nail	ST5.5×25	Configure as request	
4	Matching bolt	M16×50	Configure as request	1 bolt +1 nut+1 spring washer +2 flat washer=1 set
5	Electric Wrench	XL-80032	1	One person standard
6	Sleeve	24mm、8mm	Each 1	Use with electric wrench
7	Manual Wrench	24mm	1	One open-ended and plum combined wrench(one person standard)
8	Angle grinder	S1M-HS1-100	1	Equipped one box of cutting slices

#### 4.7 The end of the Frame Fragment Protection

The fragment are protected by shaped protective net, and the protection net at the corridor entrance without permission after installation. (Fig. 4.7.1) Installation standard:

Wear safe belts for installation. For convenience, it is preferable to install the 7-shaped bolt on the outer side of the rack, and then install the 7-shaped bolt on the inner side of the rack.



(Fig. 4.7.1)

#### **Materials and Tools**

S/N	Description	Model	Qty	Remark
1	End protection net	700×1500	Configure as request	
2	7-shaped bolt	Ф10×120	Configure as request	

#### 4.8 Installation of Skirting Board

To installed skirting board between the walkway plate and protection net when set turning plate in the frame.

Installation Standard:

Wear seat belts for installation. The installation of the skirting board should be tight, and the outer side should be close to the protective net, and the gap no more than 10 mm. When encountering interference with the pole, the opening can be avoided according to the situation to ensure the outer side is tightly closed. Under the skirting board, fix it on the outside of the skirting board with ST4.8 19 self-tapping nails. Skirting board shall be installed in a smooth way without warping and deformation (as shown in Fig. 4.8.1).



(Fig. 4.8.1)


S/N	Description	Model	QTY	Remark
1	Skirting board	1.41M	Configure as request	
2	Electric Wrench	XL-80032	1	One person standard
3	Sleeve	8mm	1	Use with electric wrench
4	Hexagonal flange self-tapping nail	ST5.5×25		
5	Angle grinder	S1M-HS1-100	1	Equipped one box of cutting slices



# Installation of Attached Support System

#### 5.1 Installation of Attached Support

Before erecting section 2 slide-way, attaching support base jack shall be installed on the frame. Firstly, inspect the pre-embedded holes are on the right position, and then the attachment support is installed in the pre-embedded holes of the structure with M30 high strength screw. Each end of the screw is equipped with one 100 x 100 x 10 Square backing plate and 2 nuts. The splints on both sides are clamped into the slide-way, and the splints are installed on the upper and lower splints of the attaching support base jack through the pin shaft of  $\phi$ 16×55 (Fig. 5.1.1). The top support and double torsion spring are installed on the surface of the attaching support base jack to make the top support stick to the slide-way. Adjust the adjusting screw of the top support to make the top support pressed on the selector.



(Fig. 5.1.1)

#### **Installation Standard:**

Wear seat belts for installation. Attachment support is installed on the outer side of the wall. The center line of the embedded hole is aligned with the center line of the slide-way, and the horizontal deviation is less than 10 mm. The movable attachment support adjusts the relative position of the attachment support and the slide-way. The tie rod nut through the wall can be tightened only after the support and cushion plate are attaching to the wall. The tie rod is forbidden to be unloaded or falsely loaded. After the backing plate is filled with the structure, the nut must be tightened to prevent loosening. The double toe rod fixed on each attachment support, and the square backing plate must be positioned horizontally. Double nuts on both sides of the tie rod, expose 3 buckle teeth or no less than 10mm. After installation, butter lubrication is applied on the contact surface between the splint and the slide-way. 3 attaching support base jack should be installed in the vertical direction of each slide-way in operation mode, and no less than 2 in lifting or descending operation mode.




(Fig. 5.1.2)



S/N	Description	Model	Qty	Remark
1	Matching manual wrench	One open-ended and plum combined wrench	1	2 persons standard
2	Attaching support base jack	Configure as request	3	
3	Top support	Configure as request	3	
4	High Strength tie rod	M30XL	6	1 tie rod+ 2 backing plate+4 nuts=1 set
5	Guide wheel frame	Configure as request	6	
6	Pin shaft	Ф16×55	12	






#### 6.1 Installation of slide-way

According to the Framing Module layout requirements, the first hole at the lower end of the slide-way is connected with the position hole of the slide-way of the walkway plate by M16 \*40 hexagonal bolt. When the two slide-way are connected, the connecting plate is needed to reinforce them.



#### **Installation of Lifting System**



are used to connect the walkway plate with the slide-way; M16 \*70 high strength bolts are used to connect the slide-way with the slide-way, and double nuts are used; M16\*40 bolts are used to connect the slide-way with the connecting plate. Due to the excessive weight of the slide-way itself, pay attention to safety during installation. 1 spring washer, 2 flat washer, 1 nut(use double nut in connect place of 2 slide-way) and 1 M16 bolt consist of 1 set, Make sure that at least 3 buckle teeth are exposed during installation. After installation, butter is applied on the contact surface between slide-way and splint. (Fig. 6.1.1)

Installation Standard: Wear seat belts for installation. M16 \*40 bolts


S/N	Description	Model	Qty	Remark
1	Slide-way	4.5m/6m	Configure as request	
2	Electric wrench	XL-80032	1	One person Standard
3	Sleeve	24mm	1	Use with electric wrench
4	Manual wrench	24mm	1	One open-ended and plum combined wrench(one person standard)
5	Matching hex bolt	M16×50	Configure as request	1 bolt +1 nut+1 spring washer +2 flat washer=1 set
6	High strength bolt	M16×70	Configure as request	1 bolt +2 nut+1 spring washer +2 flat washer=1 set



# 6.2 Installation of Upper and Lower Hanger Frame (Fig6.2.1)

Installation of Lower Hanger Frame: According to the drawing design, the hanger fixing piece and the lower hanger are reinforced together by M16 bolts and filled with bolts (as shown in Figure 6.2.2).

Installation of Upper Hanger Frame: According to the drawing design, the hanger fixing piece and the upper hanger are reinforced together by M16 bolts and filled with bolts (as shown in Figure 6.2.3).




S/N	Description	Model	Qty	Remark
1	Electric wrench	XL-80032	1	One person Standard
2	Sleeve	24mm	1	Use with electric wrench
3	Manual wrench	24mm	1	One open-ended and plum combined wrench(one person standard)
4	Matching hex bolt	M16×50	Configure as request	1 bolt +1 nut+1 spring washer +2 flat washer=1 set
5	Lower hanger	Configure as request	1	QTY for single framing module

# 6.3 Installation of Lifting Hang ing Bracket

Fix the lifting hanging bracket on the building structure with 2 high-strength screw, tighten the nut internally after adjusting the position, and tighten the external nut. The two ends of the screw leak out of the double nut at least 3 buckle teeth(no less than 10mm) (Fig. 6.3.1).

Installation Standard: Wear safty belts for installation. Installation to ensure that the lifting hanging bracket is vertical, both inside and outside are equipped with  $100 \times 100 \times 10$  backing plate, screw inside and outside must have 2 nuts.



(Fig. 6.3.1)

S/N	Description	Model	Qty	Remark
1	Matching manual wrench	One open-ended and plum combined wrench	2	2 persons standard
2	High strength screw	M30XL	2	1 bolt+ 2 backing plate + 4 nut=1 set
3	Lifting hanging bracket	Standard specification	1	
4	Loading pin shaft	24mm	1	attaching split pin




# 6.4 Load Sensor and Electric Chain Hoist Installation

Load sensor is installed at the hanging point of the lower hanger frame, which is tightened and strengthened with M30 \*120 high strength standard bolts, nuts, spring washer and flat washer. (Figure 6.4.1)

The electric chain hoist hook is hung in the hanging hole above the sensor, and the upside chain unit of the electric chain hoist is installed on the upper hanger. (Figure 6.4.2)

#### Installation Standard:


Wear seat belts for installation. When the electric chain hoist is suspended, the wire that binds the chain is not allowed to be dismantled. After the complete installation, the chain should be dismantled. The chain should be straightened out. There should be no phenomenon of chain flipping, twisting, knotting and crossing rings that affect the operation. After the installation, butter should be applied to the chains, springs, screw and other positions.





(Fig. 6.4.2)

S/N	Description	Model	Qty	Remark
1	Matching Manual wrench	46mm/41mm	2	One end 46mm and another end 41mm (2 persons standard)
2	Load sensor	10T	1	
3	Electric chain hoist	7.5T	1	
4	High strength screw	M30×120	1	1 bolt+ 2 backing plate + 4 nut=1 set





# **Installation and Use of Control System**

#### Installation of Electrical Control System

The electrical installation of GT-18 Self Climbing Platform should strictly comply with the provisions of "Code for Safety of Power Supply in Construction Site" GB50194 and "Technical Code for Safety of Temporary Electricity Use in Construction Site" JGJ46.

- 7.1 The cable is protected by special PVC groove, fixed on the protective network of the lower side of the second walkway board, and the main cable is distributed within the same height. The reserved length of the cable should meet the requirement of raising the height of one layer. The cable joint must be securely tied by insulating waterproof tape, and the connection should be firm and reliable, so as to avoid false connection and leakage connection.
- 7.2 Main Control Box and Sub-control Box should be waterproof. The main control box and sub-control box shall meet the safety requirements of grounding and leakage protection, and the main control box and sub-control box shall be installed in the first step of the frame.
- 7.3 The control mode of electrical system is divided into automatic control (remote control) and manual control.

Automatic control refers to the use of remote to control the main control box, so as to achieve the controlling the rotation of each electric chain hoist. Manual control refers to the failure of some positions, which affects the overall lifting of the whole rack. At this case, it is necessary to control the operation of a certain position separately, eliminate the failure and ensure the overall lifting of the rack.

Connecting the wire-controlled air plug with the air socket of the control box, the remote controller can be used to control the forward, reverse and stop of the electric chain hoist.



S/N	Description	Model	Qty	Remark
1	Mai control box	Standard specification	Configure as request	
2	Sub-control box	Standard specification	1	QTY for single framing module
3	Cable	Standard specification	Configure as request	
4	PVC groove	Standard specification	Configure as request	
5	Cable ties	5X400	Configure as request	
6	Controller	Standard specification	1	
7	Electrician knife	10-225-23	1	
8	Multimeter	3280-10F	1	
9	Test pencil	MNT -111302	1	
10	Insulating waterproof tape	25x500mm	10	Insulation before waterproof tape
11	Electrical insulat- ing tape		10	
12	Vice	FO-2603A	1	
13	Wire stripper	LA815138	1	
14	Slot type screw- driver	JX-0189	1	
15	Phillips screw- driver	JX-0189	1	
16	Scissors	45-degree angle scissors multifunctional electrical trough scissors universal PVC scissors		
17	Electric Box Installa tion Auxiliary Frame			



8
Lightning Protection System Installation

# **Lightning Protection System-In stallation**

## 8.1 The Lightning Protection System Consists of A Lightning Receptor, Lightning Protection Net and Grounding Wire.

8.1.1 Lighter (i.e. lightning rod) Made of  $\phi$ 12 × 1200 galvanized steel.

#### 8.1.2 Lightning protection net

All the lightning receptors on the uppermost layer are connected by  $40 \times 4$  galvanized flat iron to form a lightning protection net.

#### 8.1.3 Ground wire

Set a grounding wire within 50m of the continuous length of the climbing frame, and meet the requirements of the transition resistance of the climbing frame  $\leq 10\Omega$  and the grounding resistance  $\leq 20\Omega$  at the farthest point from the grounding wire. A grounding wire is arranged under the pole, and the grounding wire is connected to the lightning protection grounding point of the construction structure by a grounding cable with a diameter of not less than 16 mm2.






### 8.2 Attention When Setting Lightning Protection Devices

- 1. After the frame is installed, the lightning protection measures and lightning protection devices during the thunderstorm season should be done.
- 2. The grounding mode and position selection, lightning protection net and grounding wire arrangement, material selection, connection method, fabrication and installation shall be installed in accordance with the "Lightning Protection Design Code for Buildings" GB50057-94. After installation, the resistance meter shall be used for determination, see whether it meets the "Technical Specifications for Building Lightning Protection Devices".
- 3. The position of the grounding wire should be selected where people can't easily touch it to avoid and reduce the risk of stride voltage, prevent the grounding wire from being mechanically damaged, and keep the grounding wire at a safe distance of 3m or more from other metals or cables.
- 4. In case of thunderstorm during construction, the personnel on the frame should be evacuated immediately (to prevent personal injury caused by lightning strikes).



# Correct Operation of the GT-18 Self Climbing Platform

## 9.1 GT-18 Self Climbing Platform lifting process





## 9.2 After The Installation of the Frame Is Completed, Notify Party A To Check and Accept

For specific matters, check the "GT-18 Self Climbing Platform First Installation Inspection Acceptance Form"

P	roject			Construction area (m²)			
Stru	ıcture	Structure floo	or	Maximum height (m²)			
	nber of Chine	promotion and demotio grouping	n	Usage			
Mai	n contractor			Project manager			
Clie	nt			Project manage			
Spec editi tion	ial program ng produc- company			Project manager			
	allation npany			Project manage			
S/N	Inspection items	Inspection	n contents		Inspection result		
1		Frame height≤5 times storey heigl	Frame height≤5 times storey height, Frame width≤1.2m				
2		Support span (straight type)≤7 m Support span (the distance outside	the fold line or curved fra	me) ≤ 5.4m			
3	Scaf-	Full height of the frame $\times$ support	span ≤110 m2				
4	folding Size	Horizontal cantilever length ≤ 2m,	and ≤ 1/2 adjacent suppo	ort span			
5		The poling, the longitudinal horizo intersect with the major node.	ntal bar and the transverse	e horizontal bar			
6		Poling spacing and cross bar spacing and current relevant standards.	ng are in accordance with t	he specifications			
7		Component layout conforms to the	instructions				
8	Vertical	The specifications and dimensions instructions for use.					
9	main frame	Each joint is welded or bolted.					
10		The vertical deviation ≤5‰, and ≤					
11		The height difference of adjacent v	ertical main frames≤20mr	m			

S/N	Inspection items	Inspection contents	Inspection result
12		Component layout and specification conforms to the instructions	
13	Horizontal support	Each joint is welded or bolted.	
14		Poling spacing is in accordance with the specifications and current relevant standards	
15		Component layout and specification conforms to the instructions and current relevant standards	
16	Frame structure	No missing parts of the frame and reliable connection	
17		The poling, the longitudinal horizontal bar and the transverse horizontal bar intersect with the major node.	
18		Connecting nodes conform to specifications and current relevant standards	
19	Scaffold-	Bearing capacity and deformation of scaffoldings conform to special safety construction scheme	
20	ing	The bottom is laid tightly, and there is no gap with the building.	
21		The operation layer is covered and laid firmly, the diameter of the tangential circle in the hole <25mm, and the length of the scaffolding probe ≤150mm.	
22		Attachment support shall be provided for each floor covered by the vertical main frame.	
23		Attachment support shall be connected with building structure by no less than two bolts, and the bolt diameter meets the design requirements.	
24		attaching support base jack and building structure are tightly combined and fastened	
25	Attaching	The age compressive strength of concrete at the joints meets the design requirements and $\geqslant\!15\text{MPa}$	
26	support base jack	Distance from center of bolt hole to bottom of beam (>150 mm)	
27		The exposed length of the bolt is more than 3 times the pitch and more than 10 mm. Size of backing plate (> $100 \times 100 \times 100$ mm)	
28		It has anti-tilt and guiding functions.	
29		Using operation mode, the frame body is fixed on the attachment support	
30		Facade full of bridging	
31	Bridging	The horizontal angle of the scissors is $45^{\circ} \sim \! 60^{\circ};$ it is reliably connected with the frame rod	
32		When the steel mesh frame is used to replace the bridging in the diagonal bar, the rigidity and strength of the diagonal bar are not lower than the rigidity and strength of the bridging, and the connection with the frame body should be ensured.	



S/N	Inspection items		Inspection contents			Inspection result
33		Anti-overturning rails are r	reliably connected to the	e vertical major frame		
34	Anti-over- turning equip-	For lifting conditions, the minimum guides is ≥ 2.8m, or ≥ 1/4 height; uppermost and lowermost anti-tilt	the working condition, the spaci	ng between the		
35	ment	The gap between the guid	e and the guide rail is ≤	5mm		
36		Each machine position is rused in both use and lifting		i-drop devices, and can b	е	
37	Anti-drop devices	anti-drop devices has dust sensitive and reliable	proof and anti-pollutior	n measures, and is		
38	3017000	When only one anti-drop of device should be connected	device is provided for one ed to the different wall so	e position, the anti-drop upport with the lifting de	vice.	
39		The steel boom of the boo tion and diameter is ≥ 25 r		es is determined by calcu	la -	
40	Synchro-	Tooled scaffolding with res	stricted load control syst	tem		
41	nizer	It has the functions of con- overload and load loss, rea	trolling lifting and lower al-time display and stora	ing, automatic alarm and age of load, and self-fault	d stop of alarm.	
42		The dense mesh safety ner plate vertical mesh apertu		², and ≥3.5kg/sheet;Met	al	
43		The facade is protected tig	thtly and without gaps.			
44	Protective	When the dense mesh is used as th foot-board. When the framed meta with the frame and can withstand I	I mesh is used as the safety net,	the metal frame should be reliab		
45	equipment	When the working floor is high protective railing is in	more than 2.0 meters av	vay from the floor, a 1.2 r	n	
46		The frame is broken or has vertical net	a protective barrier at t	he opening or closed wit	h a	
47		The diameter of the inscribed circle should be less than 25mm; the scal body should be completely closed	folding board at the bottom of t			
			Acceptance			
Inspectio conclusio						
Inspe	Special program pector's signature Main contractor Client editing production Construction company					uction company
	Date:					

## 9.3 Scaffolding Lifting (Or Lowering) Must Be Approved By Party A

Details refer to GT-18 Self Climbing Platform Pre-Lift inspection and acceptance form

Pi	roject		Operational type	hoist
Work	king layer	hoist height (m)		
Main	contractor		Project manager	
(	Client		Project manager	
Spec editi tion	ial program ng produc- company		Project manager	
Cons	truction pany		Project manager	
S/N	Inspection Item	Inspection content		Inspection result
1	Concrete strength at the attaching support base jack	Reach the calculated value of the safety sp	pecial construction plan, and ≥15MPa	
2		Frame height≤5 times storey height, Fran		
3		The frame has no structural changes, miss	ing components, and damage.	
4	Scaffolding condition	The components of the frame are connect connection is reliable.	ed without missing and the	
5		The unloading device at the vertical major can not use fastener or wire rope shall be	r frame shall not be less than 2, and used as the unloading device.	
6		The safety protection facilities are not dar	naged.	
7		attaching support base jack for each exist the vertical major frame	ing floor covered by	
8	Attaching support base jack	The anti-drop, anti-roll and guide devices support base jack are intact.	on the attaching	
9	base jack	attaching support base jack adapt double	nut to reinforced.	
10		The lifting device is set up at the vertical n		
11	Lifting	Lifting support adapt double nut to reinfo		
12	equip- ment	The connection of the lifting system comp and the connection is firm.		
13		The lifting system is cleaned, maintained	and runs smoothly	



S/N	Inspection items		Inspection contents			Inspection result
14	Lifting	The power equipment of relevant standards, and the startup is sensitive, a	the suspension is correc	t. the connection is relia	rent ble,	
15	equip- ment	The control cabinet and functional.	control equipment are v	vorking properly and full	ly	
16		Each machine position i equipment, and it can fu	s not less than one set of inction in both use and l	f anti-overturning ifting conditions.		
17	Anti-over- turning	Anti-overturning equipn	nent completed, Working	g condition is normal		
18	equipment	After cleaning, inspectio sensitive and reliable.	n and maintenance, it is	easy to operate,		
19		The installation position	is correct and the stop i	s effective.		
20	Anti-drop	For lifting conditions, th most guides is ≥ 2.8m, o distance between the up	e minimum distance bet or ≥ 1/4 height; in the w opermost and lowermost	ween the uppermost and orking condition, the mil t guides is ≥ 5.6m, Or ≥	d lower- nimum 1/2 height.	
21	device	The cantilever height of	the frame is ≤ 2/5, and	≤ 6m		
22	Obstacle	Obstacles and restraints	of unobstructed scaffold	ding are lifted		
23	Constraint removal	All the wall bars on the f	rame are removed			
24	Operators	Hold a certificate and ha	ive a Safety and Technol	ogy Training record		
25	Command,	Unified command, perso equipment working pro	onnel in place, clear resp perly	onsibilities,		
26	communi- cation, security	Lifting action sound and	light prompts work nor	mally		
27	alert	Have a security guardiar	nship area and have a de	dicated person		
28	Cable line and switch box	It meets the calculation industry standard "Safet Construction Sites"; set	requirements for line loa cy Technical Specificatio a special switch box.	ad in JG46 of the current ns for Temporary Use of		
			Acceptance			
Inspection conclusion	spec- on Rectifi- onclu- cation					tion, acceptance
	Inspector's signature	Main contractor	Client	Special program editing produc-tion company		onstruction ompany
	Date:					


### "GT-18 Self Climbing Platform Pre-Down Inspection and Acceptance Form"

Р	roject		Operational type	hoist, decline			
Wo	rking layer	Decline height (m)	Decline height (m) Decline grouping				
Mai	in contractor		Project manager				
Clie	ent		Project manager				
Spe edi tior	ecial program ting produc- n company		Project manager				
	nstruction npany		Project manager				
S/N	Inspection Item	Inspection content		Inspection result			
1	Concrete strength at the attaching support base jack	Reach the calculated value of the safety special construc	tion plan, and ≥15MPa				
2		Frame height≤5 times storey height, Frame width≤1.2n	า				
3		The frame has no structural changes, missing componer	ts, and damage.				
4	Scaffolding condition	The components of the frame are connected without mis connection is reliable.	ssing and the				
5		The unloading device at the vertical major frame shall no not use fastener or wire rope shall be used as the unload	ot be less than 2, and can ing device.				
6		The safety protection facilities are not damaged.					
7		attaching support base jack for each existing floor covere the vertical major frame	ed by				
8	Attaching support base jack	The anti-drop, anti-roll and guide devices on the attachin support base jack are intact.	ng				
9	Dase Jack	attaching support base jack adapt double nut to reinforc	ed.				
10		The lifting device is set up at the vertical major frame					
11	Lifting	Lifting support adapt double nut to reinforced.					
12	equipment	uipment The connection of the lifting system components is not cracked, damaged, and the connection is firm.					
13		The lifting system is cleaned, maintained and runs smoo	thly				



S/N	Inspection items		Inspection contents			Inspection result	
14	Lifting	The power equipment of relevant standards, and the startup is sensitive, a	complies with the instru the suspension is corre and the operation is norr	ction manual and the cect, the connection is renal.	current eliable,		
15	equip- ment	The control cabinet and functional.	control equipment are w	vorking properly and ful	ly		
16		Each machine position i ment, and it can functio	s not less than one set of n in both use and lifting o	anti-overturning equip- conditions.	-		
17	Anti-over-	Anti-overturning equipn	nent completed, Working	g condition is normal			
18	turning equipment	After cleaning, inspection reliable.	n and maintenance, it is	easy to operate, sensitiv	e and		
19		The installation position	is correct and the stop is	s effective.			
20	Anti-drop	For lifting conditions, the most guides is ≥ 2.8m, distance between the up	he minimum distance bo , or ≥ 1/4 height; in the opermost and lowermost	etween the uppermost e working condition, the guides is ≥ 5.6m, Or ≥	and lower- e minimum 1/2 height.		
21	device	The cantilever height of	the frame is ≤ 2/5, and •	≤ 6m			
22	Obstacle, constraint	Obstacles and restraints	of unobstructed scaffold	ling are lifted			
23	removal	All the wall bars on the f	rame are removed				
24	Operators	Hold a certificate and ha	ave a Safety and Technol	ogy Training record			
25	Command,	Unified command, perso equipment working pro	onnel in place, clear resp perly	onsibilities,			
26	communi- cation, security	Lifting action sound and	l light prompts work nor	mally			
27	alert	Have a security guardian	nship area and have a de	dicated person			
28	Cable line and switch box	It meets the calculation industry standard "Safe Construction Sites"; set	n requirements for line l ety Technical Specificat a special switch box.	oad in JG46 of the cur ions for Temporary Us	rent e of		
			Acceptanc	e			
Inspection conclusion	Rectifi- <sub>J-</sub> cation	Rectifi-					
	Main Client Special program editing production company					uction company	
					Date:		

### 9.4 Pre-Tightening Electric Hoist Steps and Methods



### 9.5 GT-18 Self Climbing Platform Requirements

Implement the principle of "safety first, prevention first".

Construction personnel shall abide by the "Safety Technical Operation Regulations for Construction and Installation Workers".

#### Lifting operation safety measures:

A:To do not raise and lower with four principles: Rain, five grades (including five grades) above the strong wind, no rising and falling; When the sight is not good, no rising and falling; No lift inspection, no rising and falling; Division of labor, responsibility is not clear, no rising and falling.

B:The warning line shall be set on the ground during lifting operations, and any unrelated personnel shall not be in the warning line.

C:When the construction site is large, sufficient walkie-talkie should be configured to strengthen communication links.

D:No personnel shall stay on the climbing frame when the climbing frame is lifted or lowered.



## **Precautions for use**

1. After the GT-18 Self Climbing Platform is assembled in one time, it enters the structural construction stage. When using scaffolding at this stage, it must be used according to the construction plan requirements and the operation method of this manual. It is necessary to offer technology disclosure for each construction team.

2.All personnel are prohibited from being put on frame during the lifting operation of the scaffolding. After the lifting is completed, the climbing frame operator checks the frame and confirms that the "GT-18 Self Climbing Platform Lifting Checklist" and the "GT-18 Self Climbing Platform Falling Checklist" (Appendix A. After the requirements of 1.4 and Appendix A.1.5), Party A shall be notified to arrange for the construction of other construction workers.

3.After the scaffolding is set up according to the design plan, it is forbidden to carry out any expansion, erection and connection activities on the scaffolding. It is forbidden to hang advertising billboards on the external frame.

4.The materials is prohibited on the frame body, and each time the concrete is finished, Party A arranges personnel to clean up.

5. When the scaffolding is in use, no one can remove the scaffolding member at will. The components of the scaffolding must not be replaced by other materials.

6.Before the scaffolding is lifted, the owner of the main control box must be designated. The operator should not talk to people during the lifting process, and should not be away from the main control box within 10 meters.

7. Scaffolding prohibits the following illegal operations during use: lifting materials by scaffolding, strolling on scaffolding, lifting and hoisting cables on scaffolding, arbitrarily removing structural parts or loosening joints, removing or moving safety measures on scaffolding, tower cranes Do not collide or pull the scaffolding frame when lifting the material, and prohibit dumping construction waste on the scaffolding aisle.

8.In the event of typhoon weather, the frame should be reinforced according to the "Typhoon Emergency Plan".

9.During the use of scaffolding, it should be checked once a month. For specific measures, see "GT-18 Self Climbing Platform Monthly Checklist"; The bolted joints, lifting power equipment, anti-rolling and anti-drop device, electrical equipment, etc, in the process of maintenance, the specific measures can be found in the "Monthly Maintenance Table".



## 10.2/A.1.4 GT-18 Self Climbing Platform Lifting Checklist

Project	Project Name		Building Height		Buildin	g Storeies	
Installat	Installation floor		Number of hoisting machines		Numbe	r of set-up	
Contrac	tor			Project manag	er		
Use Co.				Project manag	er		
Special	programming Co.			Project manag	er		
Installat	ion Co.			Project manag	er		
No.	Inspection Item			Content			Results
1		Techi	nical disclosure record				
2		No m	issing, changing or dam	naged components			
3		No da	No damage, obvious deformation, broken welding of the components				
4		No m	No missing or loose connection bolts				
5	Frame situation	The s	The sundries and construction waste on the frame have been cleaned up.				
6		The b	The bolt with the building structure has been released or re-fixed			d	
7		The c has b	constraint between the r leen released or reinstal	ail and the attaching sup led	port base	jack	
8		The c	constraint affecting the l	ifting operation has beer	n released		
9		Obsta	acles that hinder lifting h	nave been removed			
10		The c requi	concrete strength at the rements and ≥15MPa	adhesion support meets	the desig	า	
11		Attachment support installation position deviation ≤ 15mm					
12	Support	The a	nttachment support is se uilding structure	ecurely mounted and fits	tightly to		
13		The s meet	upport is fixed by twin t the requirements.	ie rod, and the nut and t	he base pl	ate	
14		Adhe funct	sion support should havion	ve anti-drop and anti- to	ppling		

No.	Item			Content			Results
15	Support		The anti-d ment supp	rop device should not be port as the lifting device	placed on the same attac	ch-	
16	anti-drog		The gap be be less tha	etween the guiding device an 5mm	e and the guide rail shoul	d	
17	and anti- toppling		The anti-d	rop device is flexible, sen	sitive, and effective.		
18	Device		Under the and lower	lifting condition, the dista most guides is ≥2.8m, or	ance between the uppern ≥1/4 height	nost	
19			The lifting equipmen	system is installed correc t and lifting system are re	tly and the power liably connected.		
20			The equip of rotation	ment at the bottom is ser is correct.	sitive, reliable, and the di	irection	
21	Lifting device ar	nd	The contro	ol cabinet is working prop	erly and has full function:	S.	
22	control system		Set a dedi	cated switch box			
23			The distrib Specificati	oution line complies with ons for Temporary Electri	the requirements of "Safe city Use at Construction S	ety Technical Sites"	
24			Command	lers and operators are rea	dy		
25			Communi	cation equipment is work	ing properly		
26	Safety		Set a warn	ing line or precautionary	measure.		
27	Protectio	on	Reliably cl	osed around the top hole	, set the fence		
28			A protectiv	ve door opening to the flo	or at the top step		
29			The gap be	etween the top platform a	and the floor is ≤ 30mm		
30			The differe	ence between the top plat	form and the floor is ≤0.	3m	
				Meet the requirements,	agree to use()		
Conclusions	Improve- ment content		After the improvement meets the requirements, agree to use ( )				
	cker nature		Contractor Use Co. Special program- ming Co. Installation Co.				stallation Co.
						Day	Month Year



## 10.2/A.1.5 Self-checking List For GT-18 Self Climbing Platform After The Falling

Project			Elevation		Layer		
Installed	Installed floor		Number of falling		Numbe machin	er of ne position	
General	contractor			Project Manager			
Use the	unit			Project Manager			
Special	programming unit			Project Manager	-		
Installat	tion Unit			Project Manager	-		
No.	Inspection Item		In	spection situation			Inspection result
1		Hav	ve technical disclosure	record.			
2		The	ere are no missing, cha	nging or damaged compo	onents.		
3		No damage, obvious deformation and open welding of components.					
4	Frame	No	No missing or loose for connection bolts				
5	situation	Deb	oris and construction w	vaste on the frame have b	een clear	red.	
6		The buil	bolt has been remove ding.	ed or reattaching to the st	ructure o	fthe	
7		The bas	constraint between the jack has been remov	ne guide rail and the attac ed or re-installed	ching sup	port	
8		Cor	nstraints affecting lift o	perations have been rem	oved		
9		Obs	stacles to the lifting hav	ve been removed			
10		The req	strength of the concre uirements and more th	ete at the abutment meet nan or equal to 15MPa	s the des	ign	
11		The	deviation of abutmen	t position is less than or o	equal to 1	.5mm	
12	Attaching abutment	The	abutment is installed	firmly, which is close to t	he buildir	ng structure	
13	abatment	The mee	e abutment is fixed by c et requirement.	double tie rod, the nut an	d washer	are all	
14		The falli	abutment shall have ย ng prevention	guiding functions for cap	sized and		

No.	ltem		Content			Results
15	Attaching abutment		e capsized prevention device is r utment as the lifting device	not mounted on the same		
16	Device of	اوم	e clearance between guide devic ss than 5mm	e and guide rail should be	е	
17	capsized and fallin preventic	6	e capsized prevention device is f	lexible, sensitive and effec	ctive	
18	preventio	Ur gu	nder lifting conditions, the space ides is more than or equal to 2.8r th the frame height	between the top and bott m, or more than or equal	tom two to 1/4	
19			rrect installation of lifting system tween power equipment and lifti	, reliable connection ing system.		
20		Po the	wer equipment starts sensitively e right direction	, operates reliably and rot	ates in	
21	Lifting dev		e control cabinet works normally	with complete functions	i	
22	system	Se	t up special switch box			
23		Dis tec	stribution lines shall comply with chnical code for temporary use o	the requirements of "safe f electricity on construction	ety on site"	
24		Co	mmand and operational person	nel are in place		
25		Th	e communication equipment is v	working normally		
26	Safety	То	place a cordon or alert			
27	Protection		e opening of the top floor should I should be set up			
28			set up a protective door opening e floor ladder			
29		or	e gap between the top floor plati equal to 30mm			
30		He tha	eight difference between the top to an or equal to 0.3m	floor platform and the floo	or is less	
			Meet the requirement an	d agree to use()		
Inspec- tion result	The rectification content		After the rectification	in accordance with the re	quirements, a	agreed to use()
Inspec	Gen Inspector sign		actor Use the unit	Special program- ming unit	Install	ation Unit
					Da	ite:



## 10.9/GT-18 Integrated Attachment Lifting Scaffolding Month Checklist

Pro	oject Name	Machine Number	
Ch	ecker	check date	
No.	Item	n	Status
1	Main frame		
2	Tie rod, nut and wire teeth		
3	The protective net is tightly closed an	nd the bottom flap is tightly closed.	
4	Frame arm height position		
5	Return spring of the needle		
6	Anti-roll device splint		
7	Attachment bearing (with or without	deformation)	
8	Lifting the hanger (with or without de	eformation)	
9	Reverse chain spring		
10	Whether the fasteners and bolts are f	fastened everywhere	
11	Working status of each control box (s	synchronized)	
12	Line laying (fixed and in good conditi	ion)	
13	Electric hoist (whether the hoist is da	amaged)	

## 10.9/Monthly maintenance schedule

No.	ltem	Content	Consequence
1	Electric hoist	Apply butter to chains and pulleys	
2	Jack	Apply butter to the jack	
3	Tie rod	Apply butter to the tie rod	
4	Flap	Repair the flaps, close to the self-tapping screws	
5	Bolt	Reinforced bolts that are not fastened	
6	Electrical equipment	Re-seal the damaged line with tight tape	

We insist on providing customers with the highest cost-effective formwork and scaffolding solutions and services.

**11**High Altitude Removal



## **High Altitude Removal**

### 11.1 Preparation Before Dismantling

- 1. Prepare the plan and submit it to the project department for review.
- 2. Prepare equipment for the removal of special spreaders, wire ropes, etc. for climbing frames
- 3. Check the bearing condition of the main stressed bolts such as the attaching support base jack.
- 4.Clean up the waste on the frame to ensure the safety of personnel during the removal process.
- 5.During the whole demolition construction process, a safety warning line shall be set on the ground. The warning range shall be 5 to 10 meters outside the area to be demolished, and should have a time schedule, e.g. some part in the morning, some part in the afternoon. And the tower crane lifting area shall be set up with special personnel to prevent non-workers from entering the demolition area. Be sure to be safe. 6.Do technology disclosure for the operator.

### 11.2 Dismantling Process



#### 11.3 Precautions

- 1.0 The professional team has similar demolition experience and is trained to be employed.
- 2.0 Conduct on-site field visits to accurately measure the demolition scope of the climbing frame.
- 3.0 The site of the dismantling team shall be disclosure on site, and the scope of demolition, construction sequence, and safety attention points shall be clearly defined to avoid cross-over operations.
- 4.0 It is strictly forbidden to drink, naked ,pay attention to the care products.
- 5.0 On-site command, supervision, operation, and warning are in place, and the requirements of the "Safety Technical Standard for Construction Tools and scaffolding" should be observed. The personnel should do:
- 5.1 Wearing belts and helmet, the spanner and straps to avoid falling.
- 5.2 Unified command, the demolition of the frame material is caught firmly, and it is strictly forbidden to throw.
- 5.3 A clear division of work, individual responsibility
- 6.0 Strictly follow the construction process:
- 6.1 Remove waste, garbage, and obstacles from the frame.
- 6.2 Thoroughly inspect the frame to ensure that the frame can be safely removed. The contents of the inspection are: the condition of each component of the frame, the force of each attachment and something like that.
- 6.3 It is strictly forbidden to carry out demolition work at 5 grade and above with strong winds or heavy rain, heavy snow, dense fog, thunderstorms and nighttime.
- 6.4 The demolition personnel must wear safety protective equipment correctly. The safety protection equipment must be connected to the building structure. It is forbidden to be attaching to the frame body. The safety officer is responsible for the on-site safety command work.
- 6.5 Dismantle from top to bottom, floor and area sequentially, it is forbidden to dismantle both top and bottom at the same time.
- 6.6 It is strictly forbidden to throw everything down during the whole process of dismantling the scaffolding.



# GT-18 Self Climbing Platform Installation and Common Use Tools

## List of Tools for Installation of GT-18 Self Climbing Platform

The number of tools listed in this table is based on 40 seats. The actual situation should be adjusted according to the current situation and the number of seats.

S/N	Name of Tool	Specification and requirement	Unit	ΩТΥ
1	Screw Jack	3 tons	pcs	1
2	Electric hand drill	220V	set	1
3	Stainless steel drill bit	Diameter 40mm	pcs	10
4	One open-ended and plum combined wrench	22mm	pcs	5
5	One hole-ended and plum combined wrench	24mm	set	8
6	Diamond hydraulic drill	40mm drilling bit	set	1
7	Safety hat	GETO	pcs	10
8	Tape measure	Meter	pcs	5
9	Wire stripper	LA815138	set	2
10	Utility knife	standard	set	3
11	Insulating waterproof tape	25x500mm	roll	20
12	Vice	FO-2603A	set	2
13	High-altitude safety belt	standard	pcs	10
14	New workman electric wrench	XL-80032	set	5



S/N	Name of Tool	Specification and requirement	Unit	QТY
15	Sleeve	24*150	pcs	5
16	Sleeve	22*75	pcs	5
17	Sleeve	8mm	pcs	5
18	Sleeve	24*75	pcs	10
19	multimeter	3280-10F	pcs	1
20	Test pen	MNT -111302 digital display	pcs	1
21	Long nose pliers	8 inch	pair	3
22	Phillips screwdriver	3*75	pair	3
23	Phillips screwdriver	6*150	pair	3
24	Slot type screwdriver	3*75	pair	3
25	Slot type screwdriver	6*150	pair	3
26	Aviation scissors	standard	pair	3
27	Angle grinder	Standard specification	set	1
28	Grinding sheet	Standard specification	box	2
29	Cutting slice	Standard specification	box	3
30	Manual chain hoist	1.5Ton, 3m	pcs	1
31	Positive and negative ratchet sleeve wrench	24mm	set	2
32	Hand painting	5005	bottle	Configure as request
33	Hand painting	Signal blue	bottle	Configure as request

S/N	Name of Tool	Specification and requirement	Unit	QТΥ
34	Cable ties	5X400		
35	Electric chain hoist	3 tons		
36	Electric hoist gear	Standard specification		
37	Electric hoist pulley	Standard specification		
38	Тар	Standard specification		
39	wrench jaws	Standard specification		
40	Tap drift holder	Standard specification		
41	wrench jaws drift holder	Standard specification		
42	Scissors	45-degree angle scissors multifunc- tional electrical trough scissors universal PVC scissors		
43	Large wrench	50mm		6
44	Large wrench	One end 41mm and one end 46mm combined open-ended wrench		2



# 13.1 Advantages

# GT-18 Self Climbing Platform is a new type of self-developed intelligent scaffolding. It has a number of national patents. The technical features and advantages of the product are as follows:

- 1. Adopt new attached support system, make the frame more safe and reliable.
- 2.Standard design.
- 3. Precise control system.
- 4. Quick and convenient disassembly and lifting.
- 5. Environmental protection, energy saving, low carbon design concept.
- 6. The body of the climbing scaffold made of new quality steel.

## 13.2 Production Comparison

1.Lifting the pedestal---Safety and Reliable



**GETO Climbing Scaffolding** 



Others

2.The lifting point is located outside the frame and does not affect the passage of personnel



**GETO Climbing Scaffolding** 



Others

#### 3. The passage is orderly, unimpeded and barrier-free



**GETO Climbing Scaffolding** 



Others



#### 4.Turning plate sealed----Close fit with the structure without gaps



**GETO Climbing Scaffolding** 



Others

#### 5. Control System---Intelligent automatic control system



GETO Climbing Scaffolding



Others

#### 6.Lower hanger---Special steel frame, safe and reliable



GETO Climbing Scaffolding



Other:



7.GETO GT-18 type self climbing paltform and the building structure adopt twin screw attachment connection, which is safer and more reliable than some peer self climbing platform that only use single screw attachment.






**GETO Climbing Scaffolding** 

Others

## 13.3 Personal Protective Equipment







## **Projects Reference**



Asteria, Melaka, Malaysia



Mesahill Phase 4, Nilai, Malaysia





Agile Embassy Garden,Kuala Lumpur,Malaysia



Tri-Zen Residential, South Asia



Office Building, Southeast Asia

